Sl. No.	Particulars	Unit	Quantity
	II Kitchen :—		
1	Earthwork excavation for foundation	C.yds.	4
2	Burnt stone in clay foundation and basement ...	,,	173
3	Burnt brick in clay superstructure	,,	279
4	Providing and fixing teakwood doors battened shutters, iron work, etc., complete as per Marryat's specification.	S.ft.	18
5	Providing and fixing teak wood windows with battened shutters, iron bars, iron fittings, etc., complete as per Marryats Specification.	,,	12
6	Teakwood work wrought and put up including wood oiling ...	C.ft.	11·66
7	Roofing with Mangalore pattern Tumkur tiles on teak reepers, the eave tiles being tied up by teak batten (2″×1″), screwed down to the rafter.	Sqr.	2·25
8	Ridge tiles set in mortar	R.ft.	15
9	Plastering with chunam mortar	Sqr	5·52
10	Flooring with 1½″ Cuddapha slabs on 3″ concrete bed and cement pointing.	,,	0·70
11	Providing and fixing burnt stone slabs 6″ thick dressed ..	S.ft.	26
12	Pointing to basement with cement	Sqr.	0·43
13	White washing two coats	,,	5·52
14	Sundries and unforeseen works	Lump	sum
15	Chunam borders over roof	R.ft.	30
16	Providing and fixing ventilating tiles each	Each	4
17	Silicate chacolate painting two coats	Sqr.	0 60
	III: *Latrine.*		
1	Constructing two latrines, one for male dispensary and another for female dispensary with the materials available for one and including dismantling the existing latrine.	Lump	sum
	IV. *Dead House.*		
1	Dismantling and reconstructing Dead House as per approved design.	Lump	sum

V. V. PATANKAR,
Executive Engineer.

MENTAL HOSPITAL, BANGALORE.

Dated 16th September 1929.

Sealed tenders, in triplicate, on half sheet foolscap size paper will be received by the Superintendent, Mental Hospital, Bangalore City, at his office up to 11 A.M., on Friday the 15th November 1929, for the supply of diet, contingent articles and weaving materials required for the use of this institution.

For details, please refer to *Mysore Gazette*, Part VI, pages 1009 to 1012, dated 12th September 1929.

F. NORONHA,
Superintendent.